INSTALLATION INSTRUCTIONS AND PARTS LIST

MODEL 477078, 477088, 477098 REGAL 7 OVAL STEPS (BOARDS ONLY) UNIVERSAL APPLICATIONS



- 1. Read instructions completely and check to make sure that all required parts (listed on the service parts list) are on hand before starting the installation.
- 2. Follow the instructions included with the specific bracket package that you are using to mount the brackets to your vehicle.
- 3. The step is pre-assembled from the factory. The serial number label is located on the front inside drivers side step assembly.
- 4. Attaching the step to the mounting bracket:
 - 4.1 Set the step on the mounting brackets, and slide each support mounting plate (item #9) inside the oval step and above each bracket.
 - 4.2 Using the supplied 5/16-18 x 1" black stainless steel hex bolt, washer, and serrated flange nut (items # 10,11&12) attach the step assembly, support mounting plate and mounting bracket.
 - 4.3 Set the step plate in the correct position and tighten all fasteners. Torque all 5/16" fasteners to 19 LB FT.

SERVICE PARTS LIST

	SERVICE TIRRES ELS I				
ITEM	PART NO.	QTY	DESCRIPTION		
1&2	552059	2	REGAL 7 OVAL STEP, LH,RH,76",477078		
1&2	552060	2	REGAL 7 OVAL STEP, LH,RH,86",477088		
1	552061	1	REGAL 7 OVAL STEP, LH,96",477098		
2	552062	1	REGAL 7 OVAL STEP, RH,96",477098		
3	109233	2	END CAP LH REAR, RH FRONT, BLK PLASTIC		
4	109232	2	END CAP RH REAR, LH FRONT,BLK PLASTIC		
5	107863	8	BOLT-CARRAIGE, 10-24 X 0.50,SST, BLACK		
6	108909	4	STEP PAD, 25" X 6.5", PLASTIC, BLACK		
7	108908	24	BOLT-CARRAIGE, 10-24 X 1.0,SST, BLACK		
8	107864	24	NUT-NYLOCK, 10-24, SST		
9	552052	8	SUPPORT MTG PLT, 11 GA, GALV		
10	106997	16	SCREW-HEX HD, 5/16-18X1.0,SST,BLACK		
11	106998	16	WSHR-FLAT, 5/16, SST, BLACK		
12	102680	16	NUT-SER FLG, 5/16-18, SST		



1200 E. Birch St. Brandon, SD 57005

REV A 31JUL12 552065 SHEET 1 OF 2 24FEB12

INSTALLATION INSTRUCTIONS AND PARTS LIST



APPLICATION:

MODEL 401443 STEP BRACKETS:



2014 GM SILVERADO & SIERA DOUBLE/CREW CAB PICKUPS **2015** GM TAHOE/SUBURBAN/AVALANCHE/YUKON/YUKON XL

- 1. READ INSTRUCTIONS COMPLETELY AND CHECK TO MAKE SURE THAT ALL REQUIRED PARTS (LISTED ON THE SERVICE PARTS LIST) ARE ON HAND BEFORE STARTING THE INSTALLATION.
- 2. ATTACH THE MOUNTING BRACKETS TO THE VEHICLE AS FOLLOWS: [SEE FIG. 1 & 2] 2.1 ATTACH THE TOP OF THE MOUNTING BRACKETS (ITEM #1 & 2) TO THE VEHICLE AS SHOWN.
 - 2.2 INSERT 5/16" MULTI-THREAD U-NUT (ITEM #7) INTO THE UPPER HOLES IN THE ROCKER PANEL (SEE FIG. 1).

(<u>NOTE: SOME VEHICLES WILL HAVE THREADED INSERTS IN THE ROCKER PANELS, AND WILL NOT REQUIRE THE INSTALLATION OF THE U-NUTS.</u>)

- 2.3 ATTACH THE TOP OF THE BRACKETS (ITEM #1 & 2) TO THE VEHICLE WITH 5/16-18 X 1.0 SCREW AND FLAT WASHER (ITEMS #5&4). HAND TIGHTEN ONLY.

 (NOTE; IF VEHICLE HAS THREADED INSERTS AS STATED ABOVE IT WILL REQUIRE A BLACK M8 X 30MM SCREW (ITEM #3)IN PLACE OF THE 5/16-18X 1.0 SCREW.)
- 2.4 INSTALL THE BLACK M8-1.25 SCREW (ITEM#3) AND WASHER (ITEM#4) PLACE PINCH WELD SUPPORT BRACKET (ITEM #8) ABOVE PINCH WELD AS SHOWN INSTALL M8 FLANGE NUT (ITEM#6) (*UNLESS THERE IS A THREADED INSERT ATTACHED TO THE VEHICLE*) THIS IS DONE ON EACH MOUNTING BRACKET. TIGHTEN ALL FASTENERS TO 19 LB FT.
- 3. ATTACHING THE STEP ASSEMBLY:

PLEASE REVIEW THE INSTALLATION INSTRUCTIONS THAT ARE INCLUDED IN YOUR STEP ASSEMBLY FOR SPECIFIC DETAILS.

SERVICE PARTS LIST


ITEM	PART NO.	QTY	DESCRIPTION		
PARTS INCLUDED IN THE BRACKET PACKAGE					
1	552725	3	MOUNTING BRACKET, RH, GRIP STEPS (PASSENGER SIDE)		
2	552726	3	MOUNTING BRACKET, LH, GRIP STEPS (DRIVER SIDE)		
3	100180	12	M8 X 30 X1.25 SCR,SST,BZP		
4	106998	12	5/16" STD FLAT WASHER SST, BZP		
5	100647	6	5/16" X 1.00" SCR ZP		
6	105859	6	M8 FLANGED NUT ZP		
7	105541	6	U-NUT 5/16" - 18		
8	551666	6	BRKT-MTG,PINCH WELD SUPPORT		



SILVERADO / SIERRA SERVICE PARTS LIST

-401443MODEL NO.

THE MOUNTING PATTERNS MAY NOT BE EXACTLY AS SHOWN.
HOWEVER THERE WILL BE ENOUGH FASTENERS TO MAKE THE APPLICATION.THE DISTANCE BETWEEN THE FIRST AND SECOND BRACKET WILL BE 24 INCHES.



3 310CT14

SHEET 2 OF


552740

SERVICE PARTS LIST

-401443MODEL NO.

SUBURBAN/TAHOE/AVALANCE

THE MOUNTING PATTERNS MAY NOT BE EXACTLY AS SHOWN. HOWEVER THERE WILL BE ENOUGH FASTENERS TO MAKE THE APPLICATION.THE DISTANCE BETWEEN THE FIRST AND SECOND BRACKET WILL BE 24 INCHES.



3 310CT14 3 OF SHEET 552740

